



NOTES:

1. ALL DIMENSIONS IN MILLIMETRES UNLESS OTHERWISE NOTED.
2. CONCRETE TO BE 35MPa AT 28 DAYS AND BE 5-7% AIR ENTRAINED.
3. CONTROL JOINTS TO BE LOCATED AT MAXIMUM INTERVALS OF 1.5m OC. CONTROL JOINTS TO BE SAW CUT TO A DEPTH OF 30mm.
4. EXPANSION JOINTS TO BE 12mm BITUMINOUS FIBRE BOARD SET AT 12mm BELOW GRADE AND FINISHED WITH CONCRETE COLOUR MATCHED POLYSULPHITE SEALANT FLUSH WITH FINISHED GRADE. LOCATE EXPANSION JOINTS EVERY THIRD JOINT AND WHERE CONCRETE MEETS OTHER HARD SURFACES AND STRUCTURES.
5. COLOURED CONCRETE TO HAVE BROOM FINISH PERPENDICULAR TO DIRECTION OF TRAVEL
6. CONTROL AND EXPANSION JOINTS TO BE BROOM FINISHED AFTER TOOLED.



**Transportation
Services**

**COLOURED CONCRETE SPLASH
STRIP FOR SIDE INLET CATCH
BASIN BOULEVARDS**

DATE: MARCH 2017

SCALE N.T.S.

REV.

X

X

SS-106